

PRKU

Used for fastening the insulation and plaster mesh to concrete frame. PRKU is embedded into concrete through insulation, plaster mesh and spacer ring. The length of PRKU is determined by insulation thickness and installation angle.

Material 3mm RST + coating. Consumption 4-8 pcs/m².

CE approved

