

THR + VLR + TS

Movement-allowing wall tie for concrete frame. Drill a 40mm deep hole and wedge with an installation tool (ASPU-R). The insulation is fastened with a counter plate (VLR). The brick tie is installed into brick seams simultaneously with brickwork.

THR length: insulation + 50mm. The size of the brick tie is determined by the brick height and air gap. Rustproof parts. Available in 4mm and 5mm. Consumption 4-8 pcs/m².

CE approved

